

VOILES	AAB REV A 27.04.2016	CLINIQUE MELUN				METRES / CADENCES					
		BAT B1 - N+1				QUANTITES					
				H T	EPAIS.		U	ML	M²/1face	M3	
	VOILES EXTERIEURS (HT ≤ 4,30m)										
			3.91	0.20		1.00	0.65	2.54	0.51		
			3.91	0.20		3.00	43.60	170.47	34.09		
			4.16	0.20		16.00	139.25	579.28	115.86		
	TOTAL VOILES EXT + HT et EPAISSEUR MOYENNES		4.10	0.20			183.50	752.29	150.46		
VOILES PREMUR SH (HT ≤ 3,80m)				H T	EPAIS,TOT	EP peau T					
		4.16	0.20	0.12	1.00	3.30	13.73	1.10			
		4.16	0.20	0.12	22.00	97.63	406.12	32.49			
		5.14	0.20	0.12	1.00	15.20	78.13	6.25			
TOTAL PREMUR		4.29	0.08		24.00	116.13	497.98	39.84			
TOTAL VOILES :						24.00	299.62	1250.27	190.30		
POTEAUX	MANNEQUINS				0.50	0.20		1.00	2.70	1.35	0.27
	POTEAUX RECTANGULAIRES				Section						
			2.51	0.40	0.41	1.00		2.03	0.41		
			3.11	0.30	0.30	1.00		1.87	0.28		
			3.11	0.40	0.40	2.00		4.98	1.00		
			3.26	0.40	0.40	2.00		5.22	1.04		
			3.56	0.40	0.20	2.00		4.27	0.57		
			3.56	0.40	0.40	5.00		14.24	2.85		
			3.58	0.40	0.40	1.00		2.86	0.57		
TOTAL POTEAUX RECTANGULAIRES							14.00	35.47	6.72		
POTEAUX CIRCULAIRES				Section							
		2.51	diamètre	0.50	1.00		3.94	0.49			
		3.56	diamètre	0.40	2.00		8.94	0.45			
		3.58	diamètre	0.40	1.00		4.50	0.45			
TOTAL POTEAUX CIRCULAIRES							4.00	17.38	1.39		
TOTAL POTEAUX :						18.00		8.11			
POUTRES	POUTRES PREFA PRECONTR.										
	Ep plancher	Largeur	Hauteur Totale	LG DEV/ML	HT / R		U	ML Total	M² Dev	M3	
	0.00	0.40	0.33	1.06	0.33		10.00	67.56	71.61	8.92	
	0.00	0.40	0.33	1.06	0.33		4.00	24.91	26.40	3.29	
	0.00	0.40	0.50	1.40	0.50		5.00	33.90	47.46	6.78	
	TOTAL POUTRES PREFA						19.00	126.37	145.48	18.99	
	POUTRES TRADI										
	Ep plancher	Largeur	Hauteur Totale	LG DEV/ML	HT / R		U	ML Total	M² Dev	M3	
	0.00	0.20	0.35	0.90	0.35		2.00	13.81	12.43	0.97	
0.00	0.20	0.37	0.94	0.37		1.00	15.82	14.87	1.17		
0.00	0.25	0.43	1.11	0.43		1.00	7.70	8.55	0.83		
0.00	0.40	0.55	1.50	0.55		1.00	6.77	10.15	1.49		
0.00	0.20	0.65	1.50	0.65		2.00	14.01	21.02	1.82		
0.00	0.20	0.67	1.54	0.67		1.00	16.02	24.66	2.15		
TOTAL POUTRES TRADI						7.00	58.10	91.67	8.42		
POUTRES PREFAB CHANTIER											
			LG DEV/ML					M² Dev	M3		
	0.40	1.38	3.16			2.00	11.03	34.86	6.09		
TOTAL POUTRES PREFAB CHANT.						2.00	11.03	34.86	6.09		
PLANCHERS	PLANCHER TRADI										
				H T	EPAIS.				M² total	M3	
				0.20	0.20				4.76	0.95	
				0.20	0.20				14.93	2.99	
				0.27	0.27				14.61	3.94	
	TOTAL PLANCHER TRADI					0.23	Ep Moyenne	34.30	7.88		
	PREDALE										
	Ep Pré dalle	Ep Totale	Portée Moyenne	Largeur	H T	D Compr	Nb		M² total	M3 comp	
	0.06	0.30	8.00	2.40	0.27	0.24	26.00		498.98	119.76	
	0.06	0.27	8.00	2.40	0.27	0.21	27.00		518.22	108.83	
0.06	0.25	8.00	2.40	0.27	0.19	31.00		577.28	109.68		
0.06	TOTAL PREDALLES				0.21	84.00		1594.49	338.27		
TOTAL PLANCHERS :								34.30	7.88		
TOTAL PLANCHERS - TREMIS :								34.30	7.88		
AUTRES PRE	AUTRES OUVRAGES				H T	EPAIS.	Largeur	U	ML	M² total	M3
	ESCALIERS PREFA							6.00			